M.R.O. 1—77,006—3-6-37.

(1) Number of pages ____________

(2) Date of repair ____________

(3) Initials of the Referencer ____________

MADRAS RECORD OFFICE.

Government of Madras.

A.D. Public Works DEPARTMENT.

G.O. No. 2945
380-381.

Press
~~Mis.~~

Dated 21-11- 1871.

Not to be folded or roughly handled

13

Proceedings of the Madras Government, Public Works Department, 21st November 1871.

No. 380. Read the following letter from the Superintending Engineer, 8th Division, to the Secretary to Government, Public Works Department, dated Madura, 3rd November 1871, No. 2,817 :—

1 Plan.
1 Estimate.
1 Specification Report.

I HAVE the honour to submit, for the sanction of Government, a plan, specification report, and estimate of Rupees 180, for constructing a temporary thatched building at Pereacolum, Madura District, for the use of the Tahsildar and his office, and to report that the Tahsildar's present Cutcherry is in such a dilapidated condition that it is impossible to put it in good order except at a very great expense, which will not now be necessary, as the construction of a new Cutcherry at that place has been sanctioned in G. O., No. 1,803, dated 7th July 1871.

2. I therefore recommend that the small outlay now required to provide the temporary accommodation which is indispensably necessary may be authorized from the current year's grant of Rupees 400, in the Provincial Budget, under "Minor New Works, Civil Buildings," for the Madura District.

No. 381. ORDER THEREON, 21st November 1871, No. 2,945.

CIVIL WORKS, No. 22.

SANCTIONED.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, 8th Division, with Specification.
,, Controller of Public Works Accounts.
,, Judicial Department.

Exd. S. T. Augustin.

Govt. of {1871} Madras

PUBLIC WORKS.

To

THE SUPERINTENDING ENGINEER,

8TH DIVISION.

&c., &c., &c.

Dated November 21st,

Recd. *Encl.*

G. O., 21st *November* 1871, *No.* 2,945.

NOVEMBER

Nos. 380-381

Building.—The plan and estimate constructing a temporary building for use of the Tahsildar's Cutcherry at Pe colum, Madura District, sanctioned.

No. 2817

Superintg. Engrs. Office 8th Dn.
Madura 3rd. November /71

3 B

From

Lieutt. Col. R. A. Roberts R.E.
Superintg. Engineer 8th Dn.

To

Colonel J. Carpendale R.E.
Secretary to Govt. D.P.W.

Sir,

Enclosures 3.
1. Plan
1. Estimate
1. Specification Report.

I have the honor to submit for the Sanction of Government, a Plan, Specification Report, & Estimate of Rupees 180, for constructing a temporary thatched building at Perreacolom, Madura District, for the use of the Tahsildar & his Office, & to report that the Tahsildar's present Cutcherry is in such a delapidated condition that it is impossible to put it in good order except at a very great expense, which will not now be necessary as the construction of a new Cutcherry at that place has

has been Sanctioned in G. O. No 1803 dated 7th July 1871.

2. I therefore recommend that the small outlay now required to provide the temporary accomodation which is indispensably necessary may be authorized from the current year's grant of Rs 400 in the Provincial Budget, under "Minor New Works Civil Buildings" for the Madura District.

I have the honor to be,
Sir,
Your Most Obedient Servt,
Richd. Roberts Lieutt. Col. R.E.
Superintending Engineer
8th Division

Civil Building New Works. 5 B

Detailed Estimate No of 1871/72

District Madura Talook Periacolum.

Work — Constructing thatched temporary Court House proposed to be built for the Tahsildar at Periacolum.

Particulars of work.	Measurements in feet and inches — Length	Breadth or thickness	Depth or Height	Contents.
Foundation to walls of the building	118	2½	2	590
Basement to Do.	118	2	2	472
Walls above	118	1½	8	1416
Total Cubic feet				2478
Deduct for 1 Doorway	4	1½	6	36
Do. on account of tile honey Comb work	77	1½	3	346½
Do. for 10 Posts	7¾	12	"	93
Total Deduction C. feet				475½
Remaining C feet mud wall				2003½
Or Cubic yards				74¼
Steps including foundation	8	3	1½	36
Total Cubic yards rough stone in mud				1⅓
Plastering basement & steps outside	126	2	"	252
Do. over steps	10	3	"	30
Do. walls Exterior	124	5	"	620
Do. Do. Interior	112	5	"	560
Total Plastering Squ. feet				1462
Deduct for 1 Doorway	4	6	"	24
Total deduction Sq feet				24
Remaining Plastering with mud Sq feet				1438
Or Squares				14⅓

Flooring building	46	10	a	460
Total Flooring with Jelly in Mud				460
Do Square				4 60/100
Roofing	73 1/2 13	10 1/2 4	—	771 3/4 52
Do	33 1/2	10 1/2		351 3/4
Total Thatched Roofing Square feet				1175 1/2
Do Square				11 3/4

Wood work

Wall plates over posts in walls	127	1/3	1/4	10 7/12
2 Diagonal beams in the centre of Hall	36	1/3	5/12	5
1 Tie beam in the Hall	13	1/3	5/12	1 29/36
2 Uprights	12	1/4	1/3	1
1 Ridge pole	6	1/4	1/4	3/8
Total Jungle wood Cubic feet				18 55/72
1 Ledged Door	4	a	6	
10 Junglewood posts each 1 foot Diatr. and 12 feet high				10
Tile honey Comb work over walls	77	"	3	231
Do Do Gable ends	39	"	2 1/2	117 1/2
Square feet of tile honey comb in Chunam				348 1/2

Civil Building — New Works.

Abstract Estimate No. of 1871/72

District Madura Talook Periaculum

Work — Constructing thatched temporary Court House proposed to be built for the Tahsildar at Periaculum.

Quantity	Description of Work	Rate	Amount	Total
74 1/4	Cyds of Mud work	0 4 0	18 9 0	
1/3	Do of new Rough stone in mud	1 4 0	1 10 8	
14 1/3	Square of Plastering with mud, cowdung and whitewashing over	0 10 0	8 15 4	
4 60/100	Square of Flooring with jelly well broken and beaten down to a thickness of 6 inches and well plastered	2 4 0	10 5 7	
11 3/4	Square Roofing with jungle wood couples, collar pieces bamboo reepers and bamboo mats, grass &ca complete	5 0 0	58 12 0	
18 56/72	Cubic feet of Country wrought wood	0 12 0	14 1 2	
1	Ledged Door with frames, hinges &ca Complete 4 x 6	12 0 0	12 0 0	
350	Square feet of honey comb tile work	0 1 0	21 14 0	
10	Jungle wood posts 1 foot diameter and 12 feet high at	1 4 0	12 8 0	
	Carried over		158 11 9	

Brought forward		158 11 9
Excavating foundation		6 " "
Sundries and Superintendence		15 4 3
Total Estimate Rupees		180 "

Madura
26-9-71

Richd Roberts Lieut Col. R.E.
Superintending Engineer 8th Dn.

[illegible]
Ag Collector

No 14 of 1871–72

Estimate for construction
a thatched temporary Cutch[illegible]
house for the Tahsildar
at Periaculum Rs 180

Compd [illegible]

9B

Enclosure No 2.

In a letter from the Supg Engr 8th Dn dated 3d November 1871 No 2817

9B

P. W. 5335/71

Recd 21st Novr 71 In No 380.

Estimate for constructing a temporary build=ing for the use of the Tahsildar's Cutcherry at Pereacolum

B

G.O. 7th July /71 No. 1055
126

Public Works 1871 Department
No. 2817

From No. 5335.

The Supg. Engineer
8th Dn.

To The Secretary to Govt.
P. W. D.

Dated 30th
Received 8th } November /71

Encls 3

Submits for the Sanction of Govt. Plan & Estimate of Rs 180 for constructing a temporary building for the use of the Tahsildar's Cutcherry at Pereacolom.

No. 2945 - 21 Novr /71

7/72 R. 182.

C. No 5335

Govt of {1871} Madras.

PUBLIC WORKS.

To the Superintending Engr
8th Division

Dated.

Recd.

Encl. 2

G. O. 21st Novr 1871, No 2945

Nos. 380 & 381

Building - The plan & estimate for constructing a temporary building for the use of the Tahsildar's Cutcherry at Pereacolum Madura Dt, sanctioned